



CIVITAVECCHIA PORT EXPANSION WORKS

Intervention strategy for the Country's economic development
(Law n.433/2001)



ROGEDIL SERVIZI SRL

CIVITAVECCHIA PORT EXPANSION WORKS




ANTE



POST (IN PROGRESS)

- 1- EXTERNAL BREAKWATER EXTENSION;
- 2-NEW RO-RO VASSEL DOCK CONSTRUCTION;
- 3-NEW PORT GENERAL SERVICES DOCK CONSTRUCTION;
- 4-NEW JETTY ON CAISSONS FOR RO-RO VESSEL CONSTRUCTION;
- 5- RO-RO TERMINAL CONSTRUCTION;
- 6-BONAUGURIO RIVER TUNNELING REGIMENTATION;
- 7-NORTH DREDGING RECLAMATION AREA CONSTRUCTION;
- 8-NORTH RUBBLE MOUND BREAKWATER CONSTRUCTION;
- 9- DREDGING WORKS.

CIVITAVECCHIA PORT EXPANSION WORKS

 NORTH RUBBLE MOUND
BREAKWATER

CAISSONS

DREDGING AREAS

 JETTY

RO-RO TERMINAL

CIVITAVECCHIA PORT EXPANSION WORKS




DIFFERENT TYPES OF CAISSONS

- Cassone A
- Cassone B
- Cassone B1
- Cassone B2a
- Cassone B2b
- Cassone B2c
- Cassone S
- Cassone S1
- Cassone S2
- Cassone S3
- Cassone S4
- Cassone L
- Cassone L1
- Cassone L3
- Cassone T
- Cassone T1 (1)
- Cassone PAC-a
- Cassone PAC-b
- Cassone PAC-c
- Cassone P3

DREDGING WORKS



CUTTER SUCTION DREDGER AMBIOREX WITH A SPECIFIC ROCK CUTTER



- 1 DREDGING OF THE BOTTOM FOR DEPTH INCREASING (-18 M) AND FOR THE FLOATING CAISSONS RIGHT POSITIONING




- 2 DREDGED SOIL-WATER MIXTURE FLOWING OVER TWO RECLAMATION AREAS NAMED NORTH AND SOUTH

CONCRETE CELLULAR CAISSONS CONSTRUCTION



THE FLOATING CAISSONS ARE CONCRETE BOX WITH CELLES, THEY WERE PREFABRICATED USING THREE SPECIAL FLOATING DOCKS



1 FORMWORK ASSEMBLY FOR INTERNAL AND EXTERNAL CELLS



2 REINFORCEMENT CAGE: BOTTOM SLAB, INTERNAL AND EXTERNAL VERTICAL WALLS. POURING THE SLAB AS A MONOLITHIC ELEMENT


CONCRETE CELLULAR CAISSONS CONSTRUCTION



3 PLACING THE REINFORCEMENT, UNDER THE CONTROL OF THE CONSTRUCTION SUPERVISOR



5 SEQUENCES 3-4 WERE REPEATED UNTIL THE TOTAL HEIGHT OF THE CAISSON WAS REACHED




4 SLIDING THE FORMS, POURING AND VIBRATING THE CONCRETE




6 AT THE END OF THE CONSTRUCTION PHASE, THE PLATFORM WERE SLID DOWN TO ALLOW THE LAUNCHING FROM THE DOCK


LAUNCHING THE FLOATING CAISSONS



7 THE CAISSON FLOATS BY ITSELF. AFTER THE LAUNCHING PHASE IT WAS MOORED NEAR THE DOCK WAITING FOR THE POSITIONING



8 EVERY CAISSON WAS PULLED BY TUGBOATS




9 THE CAISSON WAS DRIVEN TO THE FINAL POSITION

FLOATING CAISSONS POSITIONING



- 10** WHEN THE FLOATING CAISSON REACHES THE FINAL POSITION, IT'S SUNK BY FILLING EVERY CELL WITH WATER



- 11** EVERY CELL IS FILLED WITH GRANULAR DRY MATERIAL (DREDGED SOIL)





- 12** THE UPPER PART OF THE CELLS IS FILLED WITH CONCRETE BY USING CONCRETE TRUCKS ON PONTOON

NEW JETTY ON CAISSONS FOR RO-RO VESSEL



1A POSITIONING THE FLOATING CAISSON FOR THE JETTY



2A ASSEMBLING PRECAST BEAMS BETWEEN THE CAISSONS FOR THE UPPER CONCRETE DECK CONSTRUCTION





3A FINAL STEP: ELECTRICAL, LIGHTS, WATER AND FIRE FIGHTING SYSTEM INSTALLATION, FENDERS, LADDERS, BOLLARDS, RINGS


NEW PORT GENERAL SERVICES DOCK



1B ROCK BERM FOUNDATION, I POSITIONING THE CAISSON JOINED, FILLING CONCRETE, GRAVEL BACKFILL SETTINGS, EMBANKMENT



2B SUPERSTRUCTURE AND CROWN WALL CONSTRUCTION WITH REINFORCED CONCRETE





3B FINAL STEP: ELECTRICAL, LIGHTS, WATER AND FIRE FIGHTING SYSTEM INSTALLATION, FENDERS, LADDERS, BOLLARDS, RINGS

CRISTOFORO COLOMBO EXTERNAL BREAKWATER EXTENSION



1c ROCK BERM FOUNDATION REALIZATION, POSITIONING THE CAISSON JOINED AND FILLING WITH CONCRETE



2c SUPERSRTUCTURE AND THE CROWN WALL CONSTRUCTION WITH REINFORCED CONCRETE




3c FINAL STEP: ELECTRICAL, LIGHTS, WATER AND FIRE FIGHTING SYSTEM INSTALLATION, FENDERS , LADDERS, BOLLARDS SETTINGS


NORTH RUBBLE MOUNT BREAKWATER



1 TETRAPOD BLOCKS: TETRAHEDRAL PRECASTED CONCRETE STRUCTURE DESIGNED TO DISSIPATE THE FORCE OF THE WAVES



2 CONSTRUCTION OF THE BREAKWATER CORE WITH DREDGING MATERIALS AND THE PROTECTION LAYERS WITH TETRAPODS



3 CONSTRUCTION OF THE INTERNAL ARMOUR WITH NATURAL ROCKS

RO-RO TERMINAL CONSTRUCTION




1 LAND RECLAMATION: EMBANKMENT FILL WITH DREDGED SOIL



3 TERMINAL PAVEMENTS REALIZATION WITH A BEARING CAPACITY OF 10 t/MQ



2 ELECTRICAL, LIGHT, FRESH WATER AND FIRE FIGHTING SYSTEMS INSTALLATION



4 TERMINAL OFFICES AND ROAD ACCESS CONSTRUCTION



www.rogedil.com
2016

ROGEDIL SERVIZI SRL
Via Ada Negri, 66,
00137 Roma, Italia
Tel. 06.82002948
Fax 06.82097772
servizi@rogedil.com
www.rogedil.com